PART B.

Constructing intercepting drains for the sewerage.

No.	Items of work		Per	Quantity
1	Earthwork excavation in gravelly soil cutting and forming	..	C. yd.	666
2	Silk pattern concrete drains	4″—(1)	R. ft.	250
		4″—(2)	,,	1,220
		6″—(6)	,,	200
		6″—(7)	,,	780
3	Regrading the existing drains with old slabs	5″—(3)	,,	488
		5″—(4)	,,	136
4	New stone revetment ..	..	C. yd.	464
5	Burnt stone in chunam ..	..	C. ft.	1,800
6	Burnt stone slab covering..	..	S. ft.	640
7	Relaying the existing drains	..	R. ft.	2400
8	Storm over flows ..	..	Each	No. 8

N. ANANDALWAR,
Executive Engineer.

WATER-SUPPLY DIVISION.

Dated 24th April 1920.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Water-Supply Division, up to 18th May 1920, for the supply of levels, measuring tapes, etc., as per list attached. The supply should be completed by the 28th May 1920.

2. Each tender must be accompanied by a deposit of Rs. 85 in cash or Government Currency Notes, as earnest money, and be superscribed "Tender for the supply of levels, tapes, etc.," in default of which, tenders will be rejected.

3. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

4. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be forfeited.

5. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

6. On acceptance of one of the tenders, the earnest the money on rejected tenders will be returned.

List of levels, tapes, etc., required for use of the Stores, of the Water-Supply Division.

Particulars	Quantity required	Remarks
Stanley's New Engineer's Dumpy Level 14″ size complete, with stand	3	
Tapes measuring 50′ in cases J. C. Mark	53	
Vulcanite stapes and batters set of (8) sets	5	

Dated 20th April 1920.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Water-Supply Division, up to 31st May 1920, for 100 tons of Sulphate Alumina of good quality, American manufacture. The supply should be completed by the end of August 1920.

2. Each tender must be accompanied by a deposit of Rs. 1,000, in cash or Government Currency Notes, as earnest money, and be superscribed "Tender for the supply of Sulphate of Alumina," in default of which, tenders will be rejected.

3. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

4. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

5. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

6. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

7. The tender should be accompanied by an analysis certificate in support of the quality of the Sulphate Alumina offered, in absence of which the tender will not be considered.

S. A. RAMASWAMI IYER,
Executive Engineer.

MYSORE DIVISION.

Dated 12th April 1920.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 15th May 1920, for improving the Vanivilas Hospital at Mysore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1921.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 480 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for improving the Vanivilas Hospital at Mysore, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for improving the Vanivilas Hospital at Mysore.

No.	Items of work	Per	Quantity
	Constructing corridor—		
1	Earthwork excavation	C. yd.	118
2	Chunam concrete	C. ft.	476
3	Burnt brick in mortar	"	5,929
4	Burnt stone slabs 6" thick	S. ft.	2,327
5	Dressing 3 lines the slab pillars	"	3,525
6	Burnt coping slab 4" thick neatly 3 line dressed and champhered	"	1,561
7	Chunam plastering	Sq.	67·66
8	Cutting groves 3" x 3" for pillars	No.	282
9	White and colourwashing, 2 coats	Sq.	67·66
10	Teakwood work wrought and put up	C. ft.	448·80
11	Roofing with 1st class Mangalore tiles on teak reepers	Sq.	96·09
12	Zinc sheet for valley	Sq. ft.	288
13	Ornamental ridge tiles set in mortar cement pointing	R. ft.	829
14	Ornamental eave board	"	1,549
15	Chunam border	"	312
16	Blue silicate painting, 2 coats	Sq.	112·0
17	Flooring with Cuddappah slab over 3" concrete and cement pointing	"	39·78
18	Providing steps and ramps wherever necessary and closing gables with brick and mortar, 4½" thick plastering complete and other sundry works.	Lump sum	
	Improving the floor of wards—		
1	Flooring with 8" sq. Marseilles tiles on mortar bed and cement pointing.	Sq.	51·95
2	Dismantling the present Aspalt floor and removing debris, etc., complete.	"	51·95
3	Opening out a gateway in the south-western corner of the compound wall with gate shutter for carrying corpse by cart from Dead House.	Lump sum	
	Miscellaneous improvement—		
1	S. M. R. rails for posts	R. ft.	128
2	Zinc wire ⅛" diameter for cross pillars to pillars for spreading cloth	Lump sum	
3	Teakwood straight round poles 3" diameter including mending and smoothening for fixing in the wall of Lenoir Boiling room.	R. ft.	72
4	Fixing the poles in walls and fixing rails of post and other sundry items required.	Lump sum	